

**Camp Singer Gym Insulation Encapsulation Services
Bid Walk Clarifications and Questions Received as of 12/11/2015
Addendum #1**

Questions:

Q: Is a bid bond required?

A: No. But a Payment and Performance Bond will be required if project exceeds \$25,000.

Q: Why is there not going to be a public bid opening?

A: This item was missed. There will be public bid opening for the project. Bid Closing per this addenda is changed to 4:30pm with a 4:35pm Bid Opening in the Administrative Services Conference Room. 915 8th Street, Suite 119, Marysville, CA 95901.

Q: Do you have a budget for this project?

A: The County does not have a specific budget amount for this project.

Q: Is the plywood to be painted after it is installed?

A: No.

Clarifications:

1. Not all five bays on the north wall are to be encapsulated. Only the four east bays immediately adjacent to the gym area. First bay on the left (west) shall be left alone.
2. Not all five bays on the south wall are to be encapsulated. Only the first three from the left (east) and the exposed portion of the fourth bay ending at the heating unit on the roof of the restroom.
3. Existing fabric attached to the middle bay on the north wall is to be removed prior to encapsulation.
4. Skylights in ceiling are not to be encapsulated. Cut and sheet around these skylights.
5. At the site tours, the contractors present indicated that a 12' x 4' 1/2" fire treated plywood is not available. Your quote shall indicate the size sheathing that will be utilized. At minimum, plywood shall be 4' x 8'.
6. 2' x 4' cross members will need to be installed in the middle of each bay to prevent sagging. Sheathing clips will not suffice.
7. Contractor shall cut or notch around existing conduit on all bays where conduit is present.